BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016 **Indent No.20566**

SCHEDULE-B

NAME OF WORK: Removal of debris and desilting of drains in Bagalagunte Ward no.14

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **K M KRISHNA SWAMY**		
				In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
1	2	3	4	5	6	7
1	Removing B.S. slab of drain and stacking with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work..	Sqm	1359	57.09	Rupees Fifty Seven and Nine Paise Only	77585.31
2	Excavation and removal of silt and silt mix with sand in slushy condition form canal bed including disposing of the same in spoil bank or on canal embankment in layers as directed etc., complete with an initial lead upto 50m complete as per specfication & as per direction of Engineer-in-charge	Cum	4575.4	192.41	Rupees One Hundred Ninety Two and Forty One Paise Only	880348.87
3	Refixing stone slabs of drains and pointing in CM 1:3 etc complete complete as per specfication & as per direction of Engineer-in-charge	Sqm	1359	70.64	Rupees Seventy and Sixty Four Paise Only	95999.76
4	J.C.B. Excavator on hire basis including JCB Operator with Helper to carryout the works on emergency as per the direction of Engineer-in-charge of the work	Days	30	6021.12	Rupees Six Thousand Twenty One and Twelve Paise Only	180633.60
5	Tractor 40 HP on hire basis including Tractor Driver with Helper to carryout the works on emergency as per the direction of Engineer-in-charge of the work	Days	80	1361.92	Rupees One Thousand Three Hundred Sixty One and Ninety Two Paise Only	108953.60
					Total	1343521.14
					Percentage	-10.40%

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer